

TRAMCON
BASICS OF MANUFACTURED CONSTRUCTION
MODULE 1 – QUIZ 1

Select the best answer for each question

- 1 Who is responsible for attaching the Data Plate to each home?
 - a. the local agencies
 - b. the plant quality manager
 - c. none of the above

- 2 A modular home is subject to
 - a. state and local building codes
 - b. Federal codes
 - c. None of the above

- 3 A manufactured home
 - a. must meet the standards of the state it will be built in
 - b. must meet the HUD code
 - c. should not meet any code

- 4 Manufactured houses usually have a more _____ structure compared to normal site-built houses.
 - a. flexible
 - b. rigid
 - c. sophisticated

- 5 _____ buy, develop and sell land, and can package the ownership or rent of lots as part of the home sale.
 - a. Turnkey retailers
 - b. Home manufacturers
 - c. All of the above

- 6 Off-line stations in a manufacturing plant _____.
 - a. are where components such as walls are assembled
 - b. do not travel and are fixed
 - c. all of the above

- 7 The size and spacing of dimensional lumber for the floor joists depends on
 - a. location of the interior partitions.
 - b. the joist span and the design loads.
 - c. the height of the ceiling.

- 8 In the floor department the wood floor system is framed in _____ position to install plumbing and electrical wiring.
 - a. a vertical
 - b. an inverted
 - c. a diagonal