

TRAMCON  
BASICS OF MANUFACTURED CONSTRUCTION  
MODULE 1 – QUIZ 2

Select the best answer for each question

- 1 The ceiling gypsum boards are attached to the roof assembly using \_\_\_\_\_.  
a. screw  
b. adhesive  
c. nail
- 2 The serial number is designed to provide specific information about the home, such as \_\_\_\_\_.  
a. the number of sections it takes to make up the home  
b. the manufacturer and the state of origin  
c. all of the above
- 3 The tubs and showers are installed prior to the wall installation because  
a. once the walls are installed in the home, it may become impossible to install large components.  
b. it allows faster installation of plumbing fixtures.  
c. moisture proofing of floor is not required anymore.
- 4 The main purpose of installing gasketing material between the sidewall and the end wall is  
a. to provide a stronger connection between the side wall and the end wall.  
b. to increase resistance of the walls to wind load.  
c. to control air infiltration through joint between the sidewall and the end wall.
- 5 The roof truss distributes the weight it carries to \_\_\_\_\_.  
a. the outside walls  
b. the footings  
c. to the interior partitions
- 6 The depth of the insulation above the ceiling will vary based on the desired \_\_\_\_\_.  
a. fire resistance  
b. thermal resistance  
c. area of the ceiling
- 7 The 4' x 8' sheets of plywood roof sheathing are set \_\_\_\_\_ to the trusses.  
a. parallel  
b. perpendicular  
c. all of the above
- 8 The purpose of dielectric strength test is to check for  
a. wiring break down.  
b. failure between the electrical conductors.  
c. all of the above